

AD-A083300

**TECHNICAL
LIBRARY**

AD

TECHNICAL REPORT ARBRL-TR-02215

ESKIMO VI MODEL TESTS

Charles N. Kingery

February 1980



**US ARMY ARMAMENT RESEARCH AND DEVELOPMENT COMMAND
BALLISTIC RESEARCH LABORATORY
ABERDEEN PROVING GROUND, MARYLAND**

Approved for public release; distribution unlimited.

Destroy this report when it is no longer needed.
Do not return it to the originator.

Secondary distribution of this report by originating
or sponsoring activity is prohibited.

Additional copies of this report may be obtained
from the National Technical Information Service,
U.S. Department of Commerce, Springfield, Virginia
22151.

The findings in this report are not to be construed as
an official Department of the Army position, unless
so designated by other authorized documents.

*The use of trade names or manufacturers' names in this report
does not constitute indorsement of any commercial product.*

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Date Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER Technical Report ARBRL-TR-02215	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) ESKIMO VI Model Tests		5. TYPE OF REPORT & PERIOD COVERED Final
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Charles N. Kingery		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS US Army Ballistic Research Laboratory ATTN: DRDAR-BLT Aberdeen Proving Ground, MD 21005		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS N/A
11. CONTROLLING OFFICE NAME AND ADDRESS US Army Research and Development Command US Army Ballistic Research Laboratory ATTN: DRDAR-BL Aberdeen Proving Ground, MD 21005		12. REPORT DATE FEBRUARY 1980
		13. NUMBER OF PAGES 62
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of Defense Explosive Safety Board 2461 Eisenhower Avenue Alexandria, VA 22331		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES This work was performed for and funded by the Department of Defense Explosives Safety Board.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Munition Magazines Sealing Techniques Scaled Model Tests Explosive Safety Structure Loading Airblast		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report contains the results from a series of high explosive tests designed to determine the blast loading from 1/50th scaled models of the type planned for exposure on Operation ESKIMO VI. A 1.27 kg charge was used to simulate 158760 kg in a full size storage magazine. Blast loading on structures located to the front, side, and rear of a donor magazine are presented. Correlation with other model studies and full scale tests were made and predictions for the blast loading to be expected on the ESKIMO VI one-half scale structures are made.		

TABLE OF CONTENTS

	<u>Page</u>
LIST OF ILLUSTRATIONS	5
LIST OF TABLES	7
I. INTRODUCTION	9
A. Background	9
B. Objective	9
II. TEST PROCEDURE	9
A. Model Magazine Design	9
1. The Donor Model	9
2. The Acceptor Models	16
B. The Test Charge	16
C. Test Instrumentation	16
1. Pressure Transducers	16
2. Tape Recorder System	19
D. Test Layout	19
1. Acceptor Model F	19
2. Acceptor Model S	19
3. Acceptor Model R	25
E. Test Matrix	25
III. RESULTS	27
A. Blast Arrival Times (t_a) at Gauge Station Locations on Models F, S, and R	27
B. Peak Overpressures (P_s) at Gauge Stations Models F, S, and R	27

TABLE OF CONTENTS (CONT)

	Page
1. Peak Overpressures Recorded on Model F	27
2. Peak Overpressures Recorded on Structure	31
3. Peak Overpressures Recorded on Model R	31
C. Overpressure Duration (t_p) at Gauge Station Locations on Models F, S, and R	37
D. Overpressure Impulse (I) at Gauge Station Locations on Models F, S, and R	37
1. Overpressure Impulse Recorded on Model F	37
2. Overpressure Impulse Recorded on Model S	41
3. Overpressure Impulse Recorded on Model R	41
IV. COMPARISONS FOR FULL-SCALE STRUCTURE	41
A. Comparison of Blast Loading on Model F	41
B. Comparison of Blast Loading on Model S	42
C. Comparison of Blast Loading on Model R	46
V. PREDICTIONS FOR ESKIMO VI	48
VI. CONCLUSIONS	50
LIST OF SYMBOLS	51
DISTRIBUTION LIST	53

LIST OF ILLUSTRATIONS

<u>Figure</u>	<u>Page</u>
1. Sketch of the 1/50th scale donor model	10
2. Photograph of the interior portion of the donor model .	12
3. Photograph of concrete roof and hinged headwall	13
4. Photograph of wooden form for shaping the earth cover . . .	14
5. Photograph of donor model with sand cover	15
6. Photograph of wooden form showing gauge mounts and cable conduit for Structure F	17
7. Charge configuration and dimensions	18
8. Instrumentation system	20
9. Test layout.	21
10. Gauge station locations on Model F	22
11. Gauge station locations on Model S	24
12. Gauge station locations on Model R	26
13. Overpressure versus time at stations F-2, F-4, and F-6 .	32
14. Overpressure versus time at stations F-3, F-5, and F-7 .	33
15. Overpressure versus time at stations S-2, S-4, and S-7 .	34
16. Overpressure versus time at stations S-3, S-6, and FF-1.	35
17. Overpressure versus time at stations R-4, R-3, and R-6 .	36
18. Overpressure versus time at stations R-1, R-5, and R-6 .	38
19. Relative locations of US and UK models, gauge stations, and explosive charge configurations	43
20. Relative locations of US models and full-scale structure, gauge locations and explosive charge configurations. .	45
21. Relative locations of US and UK models, gauge stations and explosive charge configurations	47

LIST OF TABLES

<u>Table</u>	<u>Page</u>
I. Dimensions of Full Size Structure and Donor Model	11
II. Gauge Distances from Ground Zero to Locations on Model Acceptors F, S, and R	23
III. Arrival Time at Gauge Station Locations on Models F, S, and R	28
IV. Peak Overpressure at Gauge Station Locations on Models F, S, and R	29
V. Overpressure Durations at Gauge Station Locations on Models F, S, and R	39
VI. Overpressure Impulse at Gauge Station Locations on Models F, S, and R	40
✓ VII. Comparison of Blast Loading on Model in front of Donor (Full-Scale)	42
VIII. Comparison of Blast Loading on Structures to the Side of Donor (Full-Scale)	44
IX. Comparison of Blast Loading on Headwall of Structures to Rear of Donor (Full-Scale)	46
X. Predictions for ESKIMO VI	49
XI. Estimate of Blast Loading on Headwall of Structure F . .	50

I. INTRODUCTION

A. Background

The Department of Defense Explosives Safety Board (DDESB) has been an advocate and sponsor of scaled model studies being conducted at the U.S. Army Ballistic Research Laboratory (BRL) for several years. It was shown in Reference 1 that blast parameters from scaled donor models as small as 1/50th of a full size storage magazine could be correlated directly with results from full scale tests. In Reference 2, a study was conducted to document the blast loading on a scaled acceptor model, using a bare high explosive charge as the donor source. The objective was to aid in the design of the field operation ESKIMO V. In Reference 3 a comprehensive study was conducted in which both a scaled donor model and scaled acceptor models were used. Consistent results were obtained. The blast loads from an accidental explosion were established for munition storage magazines located at the current safe separation distances.

B. Objective

The objective of this project is to determine through the use of scaled models the blast loading that might be expected on the smokeless Powder/Projectile, Type II-B Munition Storage Magazine. The results will be used to design the field operation ESKIMO VI in which 1/2 scale storage magazines will be tested.

II. TEST PROCEDURE

The test procedure followed to meet the stated objective was first to design and construct the models; second, design the explosive source; and third, select the instrumentation system.

A. Model Magazine Design

The design and construction of the donor and acceptor models are described in the following sections.

1. The Donor Model

The donor models designed for this project were a 1/50th scale of the full size magazine. A sketch of the magazine is shown in Figure 1.

¹C. N. Kingery, G. A. Coulter, G. T. Watson, "Blast Parameters from Explosions in Model Earth Covered Magazines", Ballistic Research Laboratory Memorandum Report No. 2680, Sept. 1976 (AD#A031414).

²Charles Kingery, "Blast Loading on Model Earth Covered Magazines", ARRADCOM Tech. Report ARBRL-TR-02092, August 1978. (AD #A061440)

³C. Kingery, G. Coulter and G. Watson, "Blast Loading on Model Munition Storage Magazines", ARRADCOM Tech. Report ARBRL-TR-02140, Feb 1979. (AD #A069086)




Figure 1. Sketch of the 1/50th scale donor model.

The dimensions associated with the letters in Figure 1 are listed in Table I for the full-size structure and the 1/50th scale model. The full-scale dimensions were taken from the Department of the Navy, Bureau of Yards and Docks Drawings 749771 through 749774 and 793751 titled Standard Magazine, Smokeless Powder/Projectile Type II B - 57 feet by 97 feet. The primary concern in the design of the donor model was the interior dimensions. Therefore, in Figure 1 the interior dimensions are stressed.

Table I. Dimensions of Full Size Structure and Donor Model

	<u>Full-Size Feet</u>	<u>Full-Size Metres</u>	<u>1/50 Scale Metres</u>
a*	95.0	28.96	0.579
b*	50.0	15.24	0.305
c*	13.0	3.96	0.079
d*	15.2	4.63	0.093
e	25.0	7.62	0.152
f	97.0	29.57	0.591
g	3.8	1.16	0.023
h	44.0	13.41	0.268
i	77.0	23.47	0.469
j	19.4	5.91	0.118
k	1.5	0.46	0.009
l	1.0	0.30	0.006
m	121.0	36.88	0.737
n	52.0	15.85	0.317

* Interior Dimensions

The interior walls and headwall of the donor model were 0.006 m ($\frac{1}{4}$ inch) masonite. A photograph is presented in Figure 2. The roof was a scaled reinforced concrete slab designed to simulate the full scale storage magazine. The interior portion of the donor model with the concrete roof is shown in Figure 3.

The donor explosive must be emplaced after the model has been constructed in the field. Therefore a portion of the headwall was cut and hinged to allow insertion of the charge and detonator. This hinged headwall is shown in Figure 3.

When preparing the donor model for firing, a wooden form was placed over the interior portion as shown in Figure 4. A special modeling sand was packed into the wooden form giving a final configuration when the form was removed, and the sand smoothed, as shown in Figure 5. The sand used for the earth cover is 80 grit, and for each 45.4kg of sand a mix of 0.908kg of Actival (adhesive), and 0.908kg of Bentonite (clay), and 0.000946m³ 20 wt motor oil (1 quart) are blended to form a special modeling sand.




Figure 2. Photograph of the interior portion of the donor model.




Figure 3. Photograph of concrete roof and hinged headwall.




Figure 4. Photograph of wooden form for shaping the earth cover.




Figure 5. Photograph of donor model with sand cover.

Changes were made during the series of tests in the material used for both the headwall and the roof. These changes will be described in the Test Matrix Section of this report.

2. The Acceptor Models

There were three 1/50th scale, non-responding acceptor models constructed of cast concrete. The exterior dimensions of the full size structure including the earth cover were scaled down for the acceptor models. Special forms were constructed for each acceptor and the gauge mounts and cable conduit were cast into the concrete. The wooden form showing the gauge mounts and cable conduit for structure Model F is seen in Figure 6. The dimensions of the acceptor model can be found in Figure 1 and Table 1 but will also be given again in Section D of this chapter.

B. The Test Charge

For this project a special charge was designed. A 158,760 kg (350,000 pound) explosive source was designated as the full size charge weight to be considered as stored in the magazine. When scaling the linear dimensions of the structure by 1/50th, then the weight of the charge must be scaled by 50^3 or 125,000. Therefore the scale charge weight should be 1.27 kg (2.80 lbs). The charge was designed in the shape of an "H" in order to cover more floor area than a hemi-cylinder or hemisphere. The charge was cast in three units and assembled prior to placement. A drawing of the charge configuration is shown in Figure 7. The material is Pentolite and the detonator is inserted in the center of the crossbar. As noted in Reference 1, the ratio of the charge weight to storage volume should be maintained when designing a model experiment to represent a full-size storage magazine. The charge weight for the full-size structure is 158,760 kg and the volume is 1895.6 m^3 giving a charge weight to volume ratio of 83.75 kg/m^3 . The scaled model charge was 1.27 kg and the volume 0.01516 m^3 giving a charge weight to volume ratio of 83.77 kg/m^3 . The ratio was maintained.

C. Test Instrumentation

The test instrumentation system consisted of piezo-electric pressure transducers and magnetic tape recorders.

1. Pressure Transducers

Piezo-electric pressure transducers were used throughout the series of tests. The PCB Electronics Inc. Models 113A22, 113A24, and 113A28 with quartz sensing elements and built-in source followers were used exclusively.




Figure 6. Photograph of wooden form showing gauge mounts and cable conduit for Structure F.




Figure 7. Charge configuration and dimensions.

2. Tape Recorder System

The tape recorders consisted of three basic units, the power supply and voltage calibrator, the amplifier, and the FM recorder. The FM tape recorder used was a Honeywell 7600 having a frequency response of 80 kHz. Once the signal was recorded on the magnetic tape it was played back and recorded on a Honeywell Model 1858 Visicorder. This oscillograph has excellent frequency response and the overpressure versus time recorded at the individual positions were read directly from the oscillograph playback for preliminary data analysis. For final analysis and reporting the magnetic tapes were processed through an analog to digital converter and then through a computer and plotting routine where the data were tabulated and plotted as overpressure and impulse versus time. The data gathering instrumentation system is shown in Figure 8.

D. Test Layout

The primary objective of this test series was to determine the blast loading on acceptor magazines located at established safe-separation distances to the front, side, and rear of a donor magazine. The safe separation distance in metres is defined as $0.8Q^{1/3}$ for magazines located to the front or rear of the donor and $0.5Q^{1/3}$ for side to side separation, where Q is the weight of explosive in kilograms stored in the magazine. The safe separation distance is measured from the interior wall of the donor to the interior wall of the acceptor. All gauge locations were measured from the geometric center of the donor magazine floor where the center of the explosive charge was placed. All charges were detonated at the center of the cross bar. The test layout showing donor and acceptor magazines is presented in Figure 9.

1. Acceptor Model F

The 1/50th scale model of the Type II acceptor magazine located to the front of the donor was designated acceptor model F. The safe separation distance $0.8Q^{1/3}$ for the 1.27 kg charge was 0.866 m. Model F was instrumented with seven pressure transducers as shown in Figure 10, with each gauge location preceded by the letter "F". All gauge positions relative to ground zero are listed in Table II.

2. Acceptor Model S

This model was placed to the side of the donor as shown in Figure 9. The side to side safe separation distance is $0.5Q^{1/3}$. The safe separation distance for the 1.27 kg explosive source was 0.541 metres. Model S was instrumented with six pressure gauges. Although originally planned for seven gauge stations, Position S-5 was deleted. Although shown in Figure 11, it was not instrumented and is not listed in Table II.






Figure 8. Instrumentation System.



NOTE: DIMENSIONS ARE IN METRES

Figure 9. Test layout.




NOTE : DIMENSIONS ARE IN METRES

Figure 10. Gauge station locations on model F.

Table II. Gauge Distances from Ground Zero to Locations on Model Acceptors F, S, and R

Gauge Station	Full-Scale		1/50th Scale	
	Metre	Feet	Metre	Feet
F - 1	44.5	146.0	0.890	2.92
F - 2	55.2	181.1	1.103	3.62
F - 3	55.8	183.1	1.116	3.66
F - 4	59.1	193.9	1.182	3.88
F - 5	59.7	195.9	1.194	3.92
F - 6	63.1	207.0	1.261	4.14
F - 7	63.6	208.7	1.272	4.17
S - 1	34.9	114.5	0.698	3.29
S - 2	46.6	152.9	0.931	3.05
S - 3	47.4	155.5	0.949	3.11
S - 4	56.4	185.0	1.128	3.70
S - 6	57.2	187.7	1.143	3.75
S - 7	66.2	217.2	1.325	4.34
R - 1	48.2	158.1	0.964	3.16
R - 2	51.2	168.0	1.024	3.36
R - 3	51.2	168.0	1.024	3.36
R - 4	51.2	168.0	1.024	3.36
R - 5	52.2	171.3	1.043	3.42
R - 6	59.1	193.9	1.182	3.88
FF - 1	59.0	193.6	1.180	3.87

NOTE: FF-1 is a free-field gauge station.



NOTE: DIMENSIONS ARE IN METRES

Figure 11. Gauge station locations on Model S.

3. Acceptor Model R

Model R was placed to the rear with the headwall facing the donor as shown in Figure 9. A separation distance of $0.8Q^{1/3}$ for a 1.27 kg charge was 0.866 metres. Model R was instrumented with six pressure gauges, four of which were on the headwall. The locations are shown in Figure 12. Distances from ground zero are listed in Table II.

E. Test Matrix

Three test firings were planned for this project but it became obvious after three shots there was a requirement for further testing because of the sensitivity of the blast propagating from the front of the donor to the confinement of the headwall. A description of the tests are described below.

Shot 1 - The headwall of the donor was hinged and lightly taped. The roof of donor model was a scaled reinforced concrete slab. Model R was inadvertently placed at a separation distance of 0.666 m, instead of 0.866 m.

Shot 2 - The headwall of the donor was heavily taped because of the excessive overpressures recorded on Model F. The donor roof was again a concrete slab and Model R separation distance was corrected to 0.866 m.


Shot 3 - The headwall consisted of two layers of $\frac{1}{4}$ inch masonite. Other donor parameters were held constant.

Shot 4 - Two changes were made on this shot. A plaster board material was used for the roof of the donor and a $\frac{1}{4}$ inch glass headwall was inserted in place of the masonite.

Because of the variation in pressure measurements on Model F and R a decision was made to plan two follow-on tests. For these tests, a modification was made to the donor model which allowed the insertion of a scaled reinforced concrete headwall in place of the masonite.

Shot 5 - This shot had a concrete roof and headwall with a slight modification of the charge configuration. The uprights of the "H" were 20.62 cm and the crossbar was 11.75 cm. The charge weight remained the same.

Shot 6 - The roof and headwall were the same as Shot 5 and the charge configuration was the same as Shots 1, 2, 3, and 4, as shown in Figure 7.



NOTE: DIMENSIONS ARE IN METRES

Figure 12. Gauge station locations on Model R.

III. RESULTS

The results will be presented in the form of tables listing shock arrival time, peak overpressure, overpressure duration, and overpressure impulse. Selected values believed most representative of the full scale conditions will also be presented in tabular form and plotted in the form of overpressure versus time at specific station locations. A separate table will be presented for each blast parameter so that direct comparisons can be made from shot to shot.

A. Blast Arrival Times (t_a) at Gauge Station Locations on Models F, S, and R

Model F was located to the front, Model S to the side, and Model R to the rear of the donor model as shown in Figure 9, with the gauge station location shown in Figures 10, 11, and 12. The blast arrival times (t_a) at gauge station locations on the three models are listed in Table III. The arrival time of the blast wave is the time interval between the detonation of the charge and the arrival of the blast wave at a specific location. It is a good indication of the repeatability of the shots as well as an indication of the magnitude of the peak overpressure.

When analyzing the t_a values listed in Table III, it is quite apparent that there is a wide variation in the shot to shot arrival times. This was expected in view of the changes made from Shot 1 through Shot 6. Average values of arrival time for Models F and S were obtained from Shots 1, 2, and 6 while on Model R they were determined from Shots 2 and 6.

B. Peak Overpressure (P_s) at Gauge Stations on Models F, S, and R

The values of peak overpressures (P_s) recorded at the gauge stations on the three models are listed in Table IV. When a gauge station recorded the arrival of two significant shocks both values are listed in the table with a "/" to separate them.

1. Peak Overpressures Recorded on Model F

In Table IV it can be seen that the peak overpressure propagating to the front of the donor and loading Model F is quite sensitive to the headwall material and charge configuration. Shots 1, 2, and 6 are considered similar and most representative of the loading to be expected on a full scale structure. Simple averages of the recorded peak overpressures for Shots 1, 2, and 6 are listed in Column 9 of Table IV.

Table III. Arrival Times at Gauge Station Locations on Models F, S, and R

Gauge Station Location	Distance From GZ m	Shot Number						SHOT
		1	2	3	4	5	6	1+2+6
		Arrival Time, t_a						3
		ms	ms	ms	ms	ms	ms	ms
F - 1	0.890	0.278	0.318	0.383	0.541	0.346	0.438	0.345
F - 2	1.103	0.400	0.431	0.528	0.581	0.477	0.549	0.460
F - 3	1.116	0.429	0.470	0.564	0.744	0.564	0.571	0.490
F - 4	1.182	0.459	0.485	0.564	0.812	0.526	0.616	0.520
F - 5	1.194	0.515	0.531	0.654	0.829	0.656	0.646	0.564
F - 6	1.261	0.515	0.546	0.646	0.897	0.594	0.673	0.578
F - 7	1.272	0.556	0.576	0.684	0.895	0.684	0.705	0.612
S - 1	0.698	0.538	0.585	0.614	0.514	0.516	0.664	0.596
S - 2	0.931	0.744	0.795	0.685	0.812	0.752	0.893	0.821
S - 3	0.949	0.740	0.765	0.699	0.857	0.872	0.955	0.820
S - 4	1.128	1.000	1.077	1.213	1.203	1.078	1.177	1.085
S - 6	1.143	1.054	1.085	1.449	1.186	1.180	1.248	1.129
S - 7	1.325	1.300	1.376	1.462	1.376	1.301	1.447	1.374
								$\frac{2+6}{2}$
FF - 1	1.180	---	1.286	1.333	1.353	1.331	1.280	1.283
R - 1	0.964	0.823	1.238	1.328	1.108	1.302	1.312	1.275
R - 2	1.024	0.893	1.316	1.401	1.165	1.338	1.333	1.325
R - 3	1.024	0.876	1.315	1.412	1.194	1.397	1.308	1.312
R - 4	1.024	0.840	1.263	1.341	1.120	1.301	1.295	1.279
R - 5	1.043	0.961	1.369	1.420	1.233	1.413	1.472	1.421
R - 6	1.182	1.092	1.541	1.621	1.361	1.549	1.568	1.555

Table IV. Peak Overpressure at Gauge Station Locations on Models F, S, and R

Gauge Station Location	Distance From GZ m	Shot Number						SHOT $\frac{1+2+6}{3}$ kPa
		1	2	3	4	5	6	
		kPa	kPa	Peak Overpressure kPa	Peak Overpressure kPa	kPa	kPa	
F - 1	0.890	---	4598	3123	2551	2977	4257	4428
F - 2	1.103	2385	1893	1411	880	1164	1795	2024
F - 3	1.116	1579	2061	1439	591	1209	1356	1665
F - 4	1.182	1758	1645	1055	912	1120	1432	1611
F - 5	1.194	1897	1729	1298	682	1249	1746	1791
F - 6	1.261	1694	1563	895	1001	670	1307	1521
F - 7	1.272	1351	1469	1129	727	1047	1189	1336
S - 1	0.698	1945	1522	1102	1404	1008	1374	1613
S - 2	0.931	790	647	521	677	570	455	630
S - 3	0.949	453	484	508	400	593	408	448
S - 4	1.128	557	427	421	473	491	308	431
S - 6	1.143	471	391	328	347	391	362	408
S - 7	1.325	364	309	285	313	353	234	302
FF - 1	1.180	---	475	388	374	405	414	$\frac{2+6}{2}$ 444
R - 1	0.964	421/691	277/499	290/544	388/784	408/730	247/478	262/488
R - 2	1.024	1175/961	867/791	607/944	1334/1201	1330	672	774/732
R - 3	1.024	593/819	378/776	338/872	470/1281	1192	331/608	354/692
R - 4	1.024	830/807	440/743	410/677	516/1230	767/1063	400/633	420/688
R - 5	1.043	1248/1000	1090/813	952/807	1222/1087	971	595/777	842/795
R - 6	1.182	288	201	238	366	299	213	207

Notes: Shot 1. Front Headwall Free Hinge - Concrete Roof - Structure R Separation
Distance 0.666 m.

Notes: (Continued)

Shot 2. Front Headwall Taped Hinge - Concrete Roof.

Shot 3. Double Front Headwall - Concrete Roof.

Shot 4. Glass Front Headwall - Wallboard Roof.

Shot 5. Concrete Headwall and Roof - Different Charge
Configuration.

Shot 6. Concrete Headwall and Roof.

Although glass is approximately the same density as concrete, it was apparently much stronger and caused some attenuation of the blast to the front relative to the masonite or concrete headwalls. Note the peak overpressures measured on Model F and Shot 4 are much lower than recorded on Shots 1, 2, (masonite headwall) or 6, on which the donor model had concrete headwalls.

An example of the overpressures versus time along the radial centerline of Model F (Gauge Stations F-2, F-4, and F-6 are presented in Figure 13 for Shot 2. Companion Stations F-3, F-5, and F-7 records from Shot 2 are presented in Figure 14.

2. Peak Overpressures Recorded on Structure S

The peak overpressures recorded on Structure S are listed above in Table IV for all six shots. Here again the values recorded on Shots 1, 2, and 6 are considered representative and average values are listed in Column 9 of Table IV. Although the donor structure had a scaled concrete roof on Shots 1, 2, and 6 the peak overpressure recorded on Structure S from Shot 6 are generally lower than the average values. No explanation can be offered for these differences. At Gauge Station FF-1 located on the opposite side of the donor from Structure S (See Figure 9) recorded a difference of ± 7 percent from the average value recorded on Shots 2 and 6.

An example of the overpressure versus time recorded at Stations S-2, S-4, and S-7 along the centerline of the roof of Structure S on Shot 2 is presented in Figure 15. Also of interest is the blast load on the doors and headwall of Structure S. This is presented in the form of overpressure versus time recorded at Stations S-3 and S-6 in Figure 16. Also presented in Figure 16 is the overpressure versus time recorded at Station FF-1 located on the opposite side of the donor at a distance slightly greater than Station S-4.

3. Peak Overpressures Recorded on Model R

The peak overpressures loading Model R are composed of many complex reflections. Any changes in any of the donor model parameters can have a significant effect on the resultant loading on the headwall of Model R. The first peak value recorded at gauge location R-1 is an indication of the magnitude of the blast wave that will be striking the headwall. Note that if the headwall thickness or hardness of the donor model is increased then more blast is propagated to the rear.

The overpressures versus time recorded on the headwall of Structure R at stations R-2, R-3, and R-4 from Shot 2 are presented in Figure 17. There is evidence from the overpressure versus time recorded at station R-4, that an incident shock wave followed by a reflected shock wave strike that position. There is also an incident and reflected shock






Figure 13. Overpressure versus time at Station F-2, F-4, and F-6.






Figure 14. Overpressure versus time at Stations F-3, F-5, and F-7.






Figure 15. Overpressure versus time at Stations S-2, S-4, and S-7.






Figure 16. Overpressure versus time at Stations S-3, S-6, and FF-1.






Figure 17. Overpressure versus time at Stations R-4, R-3, and R-6.

with a shorter time interval between than that which is recorded at Station R-3. At Station R-2 the record indicates it may be at, or slightly below, the mach reflection triple point.

In Figure 18 the overpressure versus time recorded at Stations R-1, located on the loading platform, R-5 located on the headwall, and R-6 located on the center of the roof, (see Figure 12) are presented. It appears that Station R-5 is also located near the triple point or slightly below it. The values of peak overpressure and impulse recorded at Station R-5 are quite similar to those recorded at Station R-2.

C. Overpressure Duration (t_+) at Gauge Station Locations on Models F, S, and R

The duration of the overpressure in a blast wave is not a precise measurement but it does indicate the length of time a structure is subjected to a positive blast load and the time at which the blast load becomes negative. The positive duration (t_+) of the blast wave for all shots are listed in Table V.

One item of interest to be noted on Structure F is that the durations recorded at Stations F-2 and F-3 are shorter than recorded at other F Stations. These stations are located near the leading edge of the roof and the combination of the expansion and rarefaction waves cause a fast decay of the peak overpressure and usually a lower impulse.

D. Overpressure Impulse (I) at Gauge Station Locations on Models F, S, and R

The impulse (I) of the blast wave imparted to the structure is one of the load parameters and is determined by intergrating the area under the overpressure versus time record. The maximum impulse should occur when the overpressure reaches zero or ambient conditions i.e., the end of the positive pulse duration. The maximum values of impulse (I) calculated from the overpressure versus time records are listed in Table VI.

1. Overpressure Impulse Recorded on Model F

The maximum positive overpressure impulse (I) determined for gauge stations on model F are listed in Table VI in units of kPa-ms. The impulse along the centerline of the roof was determined from Stations F-2, F-4, and F-6. It is of interest to note that although the peak overpressure decreases while traveling from Station F-2 to F-4 to F-6, the impulse increases. This increase is in the order of 25 percent. Gauge Station F-1 was in an extremely harsh environment i.e., the fireball. Detonation products and debris, therefore, made meaningful impulse values very difficult to determine.






Figure 18. Overpressure versus time at Stations R-1, R-5, and R-6.

Table V. Overpressure Duration at Gauge Station Locations on Models F, S, and R

Gauge Station Location	Distance From GZ m	Sheet Number						AVERAGE
		1	2	3	4	5	6	1+2+6
		Overpressure Duration, t_+						3
		ms	ms	ms	ms	ms ⁺	ms	ms
F - 1	0.890	--	0.94	0.55	--	0.89	--	--
F - 2	1.103	0.65	0.63	0.96	0.90	0.87	0.86	0.71
F - 3	1.116	0.48	0.50	0.51	0.57	--	0.42	0.47
F - 4	1.182	0.94	0.87	1.18	0.98	0.89	0.83	0.88
F - 5	1.194	1.16	1.45	1.13	1.94	0.85	1.02	1.21
F - 6	1.261	1.19	1.01	1.09	1.00	1.14	1.08	1.09
F - 7	1.272	1.24	1.08	1.14	0.55	0.57	0.98	1.10
S - 1	0.698	0.71	0.55	0.62	0.59	0.63	0.59	0.62
S - 2	0.931	1.28	1.10	0.75	0.87	0.75	0.80	1.06
S - 3	0.949	0.83	1.02	1.00	0.94	0.52	0.48	0.78
S - 4	1.128	1.17	1.40	1.17	1.25	1.19	1.22	1.26
S - 6	1.143	0.81	1.10	1.06	1.15	0.76	0.68	0.86
S - 7	1.325	1.02	0.95	0.87	0.94	1.24	1.07	1.01
								$\frac{2+6}{2}$
FF - 1	1.180	--	1.25	1.32	1.22	1.11	1.18	1.22
R - 1	0.964	0.77	0.86	0.89	0.88	0.90	0.96	0.91
R - 2	0.024	0.69	0.72	0.76	0.69	0.72	0.66	0.69
R - 3	1.024	0.74	0.77	0.79	0.72	0.66	0.68	0.72
R - 4	1.024	0.55	0.71	0.71	0.65	0.72	0.66	0.68
R - 5	1.043	0.67	0.74	0.81	0.67	0.76	0.74	0.74
R - 6	1.182	0.94	1.03	0.99	0.94	0.94	1.07	1.05

Table VI. Overpressure Impulse at Gauge Station Location on Models F, S, and R

Gauge Station Location	Distance From GZ m	Shot Number						SHOT
		1	2	3	4	5	6	1+2+6
		Overpressure Impulse, I						3
		kPa-ms	kPa-ms	kPa-ms	kPa-ms	kPa-ms	kPa-ms	kPa-ms
F - 1	0.890	---	510	399	421	---	---	---
F - 2	1.103	233	183	190	121	162	164	193
F - 3	1.116	191	184	182	84	---	104	160
F - 4	1.182	261	220	223	108	147	174	218
F - 5	1.194	293	278	249	94	156	162	244
F - 6	1.261	305	230	222	159	141	183	239
F - 7	1.272	294	195	189	90	115	145	211
S - 1	0.698	208	169	153	179	152	142	173
S - 2	0.931	118	104	99	96	76	60	94
S - 3	0.949	129	114	114	83	77	56	100
S - 4	1.128	127	136	113	117	94	77	113
S - 6	1.143	138	130	117	124	79	70	113
S - 7	1.325	102	89	80	91	90	77	89
								$\frac{2+6}{2}$
FF - 1	1.180	---	110	106	109	98	105	108
R - 1	0.964	184	177	184	220	208	169	173
R - 2	0.024	266	245	239	310	291	185	215
R - 3	1.024	235	223	223	282	267	174	198
R - 4	1.024	282	203	196	258	263	161	182
R - 5	1.043	255	230	229	280	249	197	214
R - 6	1.182	107	91	92	108	91	90	91

2. Overpressure Impulse Recorded on Model S

The overpressure impulse loading the roof and headwall of Model S was reasonably consistent. If an acceptor magazine is designed to survive the loading to the front of the donor (Model F), then it will be quite hard enough to survive in the side-to-side configuration.

The overpressure impulse loading on the doors and headwall of Model S is within the same range as that loading the roof. The average impulse load on the headwall and roof is 102 kPa-ms \pm 11 percent. This is less than half the magnitude of the impulse load recorded on the roof of Model F.

3. Overpressure Impulse Recorded on Model R

The primary concern of loading on Model R is the blast loading on the headwall and doors. Gauge positions R-2, R-3, and R-4 were placed along a vertical centerline of the headwall to document any difference in the impulse load from top of the wall to the bottom. The same trend as reported in Reference 3 was noted on this project, i.e.; the impulse increases from the top to the bottom of the wall. Station R-5 was located at the center of the door at the right side of the headwall, slightly lower than R-2. It appeared to be below the triple point, therefore inside the Mach region. The impulse value at R-5 was always quite similar to that recorded at R-2.

Only one position was instrumented on the roof because the blast load was expected to be lower than recorded on either Model F or Model S.

IV. COMPARISONS FOR FULL-SCALE STRUCTURE

This series of tests with 1/50th scale models was conducted in order to give the design engineers and field test project officers the values of peak overpressure and impulse that might be expected on the planned ESKIMO VI. Comparisons of these model tests with other available model and full-scale tests will be made on a full-scale basis.

A. Comparison of the Blast Loading on Model F

The comparison of the peak overpressure and impulse from this series of tests will be made with those recorded on a test series conducted by the United Kingdom using 1/10th scale models and reported in Reference 4, and 1/50th scale US models reported in Reference 3. The UK models are

4UK Report "Blast and Projections from Model Igloos", Report No. ETN 124-76, Proof and Experimental Establishment, Shoeburghness, 1976.

described in Reference 3 where other comparisons were made. There are many difficulties in making comparisons with other test series, such as the UK tests, because the charge weight to volume ratios are different by a factor of over 2.5. The geometries of the floor areas are different and the charge configurations are different. The relative location of the donor and acceptor models, the gauge locations, and the charge configurations are shown in Figure 19. With these differences in mind, a comparison of overpressures and impulses on the structure located to the front of the donor is made in Table VII.

Table VII. Comparison of Blast Loading on Model in Front of Donor
(Full-Scale)

Reference	Charge Weight kg	Station Number	Distance from GZ m	Peak Overpressure kPa	Overpressure Impulse kPa-ms
3	133250	A - 4	58	1150	6550
*	158760	F - 2	55	2024	9650
4	216000	UK - 3	59	910	7520
3	133250	A - 6	71	662	7750
*	158760	F - 6	63	1521	11950
4	216000	UK - 4	74	1331	7580

*current model

The blast propagating to the front of the current model is much greater in both peak overpressure and impulse than that recorded in the UK trials, or the earlier US model studies from Reference 3. This may be partially accounted for in the charge configuration in that the long axis of the "H" shaped charge was parallel with the headwall on the current US tests and perpendicular to the headwall on the UK trials. (See Figure 19.) In Reference 3 the charge was a hemi-cylinder with the long axis parallel to the side walls of the magazine. With all of these differences noted, it is of interest that the impulse in the blast increases while traveling from the rear of the structure to the front of the structure even though the radial distance from ground zero is increasing.

B. Comparison of Blast Loading on Model S

The comparison with results from Model S will be made with oval arch magazines. Both full-scale and 1/50th scale results will be used. Data from Reference 3 and Reference 5, and the current series are listed in Table VIII. Relative gauge station locations are shown in Figure 20.

⁵F. H. Weals, "ESKIMO III Magazine Separation Tests", Naval Weapons Center Report NWC TP 5771, February 1976.




Figure 19. Relative locations of US and UK models, gauge stations, and explosive charge configurations.

Table VIII. Comparison of Blast Loading on Structure to the Side of Donor (Full-Scale)

Reference	Station Number	Distance From GZ m	Peak Overpressure kPa	Overpressure Impulse kPa-ms	Scaled Overpressure Impulse $I/Q^{1/3}$ kPa-ms/kg ^{1/3}
5	2	22.6	830	5540	112
3	B-1	24.8	940	7020	137
*	S-1	34.9	1613	8650	160
5	5	28.7	1140	4670	95
5	6	31.7	550	3650	74
*	S-2	46.6	630	4700	87
3	B-4	33.6	430	5650	111
*	S-4	56.4	431	5650	104
5	11	37.8	560	4290	87
*	S-7	66.2	302	4450	82
5	10-A	33.8	510	4250	86
3	B-2	35.9	520	4640	91
*	S-3	47.4	448	5000	92
5	10-B	39.6	410	4090	83
*	S-6	57.2	408	5650	104

NOTES: Reference 5 119652 kg Tritonal equivalent
Reference 3 133250 kg Pentolite
*Current Test 158760 kg Pentolite




Figure 20. Relative locations of US models and full scale structures, gauge locations, and explosive charge configurations.

It should be noted that although the "safe separation" distances are consistant, the distance from the center of the charge to the gauge location is much greater on the current series of tests. The comparisons made in Table VIII appear quite consistant and imply that the average peak overpressure on the roof will be 484 kPa (70 psi) and the impulse will be 4732 kPa-ms (686 psi-ms). The average peak overpressure loading on the headwall is 459 (67 psi) and the impulse is 4726 kPa-ms (685 psi-ms). The overall blast loading on the top of the earth cover of a storage magazine in the side to side configuration is approximately the same as the loading on the headwall. This is also borne out in the scaled values of impulse listed in Table VIII where the average scaled impulse on the roof is $90.8 \text{ kPa-ms/kg}^{1/3}$ and on the headwall is $91.2 \text{ kPa-ms/kg}^{1/3}$.

C. Comparison of the Blast Loading on Model R

The doors and headwall of the acceptor model are the most vulnerable to blast loading when located to the rear of the donor. The relative gauge station locations on the current model and the models used in References 3 and 4 are shown in Figure 21. A comparison of the results full-scale from the three different test configurations is given in Table IX. The five gauge stations used in the comparisons are C-4, R-3, and 19; also, C-2 and R-5.

Table IX. Comparison of Blast Loading on Headwall of Structures to the Rear of the Donor (Full-Scale)

Reference	Explosive Weight kg	Station Number	Distance From GZ m	Peak Overpressure kPa	Overpressure Impulse kPa-ms
3	133250	C-4	51	415/1040	9080
*	158760	R-3	51	354/692	9900
4	216000	19	53	421/834	9640
3	224000	C-4	58	404/1092	11020
3	133250	C-2	51	511/782	7280
*	158760	R-5	52	842/795	10700
3	224000	C-2	58	523/853	8050

*Current Test Series

It is difficult to make a valid comparison of the peak overpressures loading the headwall of a structure to the rear of a donor because of the complex shock reflection pattern. From the recordings made on this series of tests (Table IV) it appears that the peak reflected overpressure on the headwall can reach over 1300 kPa (13 bar or 189 psi) with an




Figure 21. Relative locations of US and UK models, gauge stations, and explosive charge configurations.

impulse (Table VI) of over 14500 kPa-ms (145 bar-ms or 2103 psi-ms). The average peak reflected overpressure on the headwall derived from Shots 2 and 6 is 749 kPa (7.49 bar or 109 psi) and the average impulse for the same two shots is 10275 kPa-ms (103 bar or 1480 psi-ms).

V. PREDICTIONS FOR ESKIMO VI

The blast load predictions for ESKIMO VI structure will be treated separately because it is planned to be a one-half scale of the full size structure. All linear dimensions of the full size structure must be divided by 2 and the charge weight must be divided by 2^3 or 8. Therefore the charge weight should be 19844 kg. In order to scale the model results to the ESKIMO VI condition, all linear distances and time must follow the following scaling technique.

$$\frac{R_{1/2S}}{(Q_{1/2S})^{1/3}} = \frac{R_m}{(Q_m)^{1/3}} \quad \text{then} \quad R_{1/2S} = R_m \left(\frac{W_{1/2S}}{Q_m} \right)^{1/3}$$

$$\text{and } R_{1/2S} = R_m \left(\frac{19844}{1.27} \right)^{1/3}, \quad R_{1/2S} = R_m \quad (25)$$

where

- $R_{1/2S}$ = distances for 1/2 scale structure
- R_m = distance for model
- $Q_{1/2S}$ = charge weight for 1/2 scale test
- Q_m = charge weight for model test

Assuming standard sea level conditions model distances, arrival time, impulse and duration must be multiplied by 25 to predict the ESKIMO VI blast parameters. The volume of the ESKIMO VI structure should be the full-scale volume 1895.6 m³ divided by 8 or 237 m³.

Predictions of the blast parameters for the ESKIMO VI test are given in Table X for pentolite at standard sea level conditions. These values should be corrected for temperature and altitude of the test site as well as any differences in the explosive charge effectiveness.

A question concerning the overpressure and impulse that would load the headwall of Model F was asked after the model tests were concluded. An estimate is made in Table XI based on the results recorded at gauge Stations A-6 and A-8 from Reference 3. See Figure 19 for relative locations.

Table X. Predictions for ESKIMO VI

Station Number	Distance From GZ m	Arrival Time ms	Peak Overpressure		Overpressure Duration		Overpressure Impulse	
			kPa	psi	ms	kPa-ms	psi-ms	
F - 1	22.25	8.62	4428	642	---	---	---	---
F - 2	27.56	11.50	2024	294	17.75	4825	700	700
F - 3	27.90	12.25	1665	242	11.75	4000	580	580
F - 4	29.55	13.00	1611	234	22.00	5450	790	790
F - 5	29.85	14.10	1791	260	30.25	6100	885	885
F - 6	31.52	14.45	1521	221	27.25	5975	867	867
F - 7	31.80	15.30	1336	194	27.50	5275	765	765
S - 1	17.45	14.90	1613	234	15.50	4325	627	627
S - 2	23.28	20.52	630	91	26.50	2350	341	341
S - 3	23.72	20.50	448	65	19.50	2500	362	362
S - 4	28.20	27.12	431	62	31.50	2825	410	410
S - 6	28.58	28.22	408	59	21.50	2825	410	410
S - 7	33.13	34.35	302	44	25.25	2225	323	323
FF - 1	29.50	32.08	444	64	30.50	2700	392	392
R - 1	24.10	31.88	262/488	38/71	22.75	4325	627	627
R - 2	25.60	33.12	774/732	112/106	17.25	5375	780	780
R - 3	25.60	32.80	354/692	56/100	18.00	4950	718	718
R - 4	25.60	31.98	420/688	61/100	17.00	4550	660	660
R - 5	26.08	35.52	842/795	122/115	18.50	5350	776	776
R - 6	29.55	38.88	207	30	26.25	2275	330	330

Table XI. Estimate of Blast Loading on Headwall of Structure F.

Reference	Charge Weight	Station Number	Peak Overpressure	Station Number	Peak Overpressure	A-8/A-6
	kg		kPa		kPa	
3	133250	A-6	662	A-8	117/276	0.18 & 0.42
*	158760	F-6	1521	F-8**	274/639***	

Reference	Charge Weight	Station Number	Impulse	Station Number	Impulse	A-8/A-6
	kg		kPa-ms		kPa-ms	
3	133250	A-6	7750	A-8	8940	1.15
*	158760	F-6	11950	F-8**	13742***	

Notes: * current test series
 ** F-8 represents headwall of Model F
 *** Predicted F-8 value full-scale

Using the ratio of the peak overpressures recorded at Stations A-8 and A-6, shown in Table XI, then predicted values can be made for F-8 based on the recorded value at F-6. This gives a first peak at F-8 of 274 kPa (40 psi) and a second maximum peak overpressure of 639 kPa (93 psi). The ratio of impulse recorded at Station A-8 and A-6 is 1.15 and therefore the predicted impulse for Station F-8 would be 11950 kPa-ms x 1.15, or 13742 kPa-ms full scale, or 6871 kPa-ms (997 psi-ms) for 1/2 scale ESKIMO VI. This estimate implies that the doors and headwall of the structure located to the front of the donor may be subjected to a higher impulse load than the doors and headwall of the structure located to the rear of the donor.

VI. CONCLUSIONS

The validity of the results from the current series of tests will not be known until after Operation ESKIMO VI. But based on the correlation obtained between scaled models and full size structures in References 1, 2, and 3 it is reasonable to believe the predictions presented in Table X will be a good estimate of blast parameters that will load the acceptor structures to be used in the ESKIMO VI field test.

LIST OF SYMBOLS

t_a	Arrival time of shock wave - ms
P_S	Peak overpressure of shock wave - kPa
I	Impulse of the shock wave - kPa-ms
t_+	Duration of the overpressure of the shock wave - ms
Q	Charge weight - kg

DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
12	Commander Defense Technical Info Center ATTN: DDC-DDA Cameron Station Alexandria, VA 22314	1	Director Weapons Systems Evaluation Group ATTN: CPT Donald E. McCoy Washington, DC 20305
1	Office Secretary of Defense Office DDR&E ATTN: Mr. J. Persh, Staff Specialist, Materials and Structures Washington, DC 20301	2	Chairman Joint Chiefs of Staff ATTN: J-3, Operations J-5, Plans & Policy (R&D Division) Washington, DC 20301
1	Director of Defense Research and Engineering Department of Defense Washington, DC 20301	2	Director Joint Strategic Target Planning Staff ATTN: JLTW TPTP Offutt AFB Omaha, NB 68113
1	Assistant Secretary of Defense (MRA&L) ATTN: ID (Mr. H. Metcalf) Washington, DC 20301	1	Director Defense Communications Agency ATTN: NMCSSC (Code 510) Washington, DC 20305
1	Assistant to the Secretary of Defense (Atomic Energy) ATTN: Document Control Washington, DC 20301	3	Director Defense Nuclear Agency ATTN: Dr. George Ullrich, SPSS DR. E. Sevin, SPSS Mr. T.P. Jeffers, OLAG Washington, DC 20305
1	Director Defense Advanced Research Projects Agency 1400 Wilson Boulevard Arlington, VA 22209	4	Director Defense Nuclear Agency ATTN: SPTL Tech Lib (2 cys) APSI (ARCHIVES) LGLS, Mr. E.L. Eagles Washington, DC 20305
1	Defense Civil Preparedness Agency ATTN: David W. Bensen Washington, DC 20301	1	Commander Field Command Defense Nuclear Agency ATTN: Tech Lib, FCWS-SC Kirtland AFB, NM 87115
2	Director Defense Intelligence Agency ATTN: DT-1B, Dr. J. Vorona DIR-4C3, R. Sauer Washington, DC 20301		

DISTRIBUTION LIST

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	DNA Information and Analysis Center TEMPO, General Electric Co. ATTN: DASIAC 816 State Street Santa Barbara, CA 93102	1	HQDA (DAEN-MCE-D/Mr. R.Wright) Washington, DC 20314
3	Director Institute for Defense Analysis ATTN: Dr. J. Menkes Dr. J. Bengston Tech Info Ofc 400 Army-Navy Drive Arlington, VA 22202	1	HQDA (DAEN-MCC-D/Mr.L. Foley) Washington, DC 20314
5	Chairman Department of Defense Explosives Safety Board Rm 856-C, Hoffman Bldg. 1 2461 Eisenhower Avenue Alexandria, VA 22331	1	HQDA (DAEN-MPE-T,Mr.R.L.Wight) Washington, DC 20314
1	Commander in Chief US Army Europe ATTN: AEAEN, LTC T. Stong APO New York, NY 09081	1	HQDA (DAPE-HRS) Washington, DC 20310
1	Commander in Chief US Army Europe ATTN: AEAGA-BE, Mr. P.Morgan APO New York, NY 09081	1	Office of the Inspector General Department of the Army ATTN: DAIG-SD Washington, DC 20310
1	HQDA (DAMA-CSM-CA) Washington, DC 20310	1	Director US Army Advanced BMD Technology Center ATTN: M. Whitfield Huntsville, AL 35807
1	HQDA(DAMA-CSM-CA, Mr. Lippi) Washington, DC 20310	1	Commander US Army Ballistic Missile Defense Systems Command ATTN: J. Veeneman P.O. Box 1500, West Station Huntsville, AL 25807
1	HQDA (DAMA-AR; NCL Div) Washington DC 20310	1	US Army Engineer Div. Europe ATTN: EUDED, Mr.N. Howard APO New York, NY 09757
1	HQDA (DAMO-NCC, COL B.C. Robinson) Washington, DC 20310	1	US Army Engineer Division ATTN: Mr. Char P.O. Box 1600 Huntsville, AL 35809
1	HQDA(DAEN-RDL) Washington, DC 20314	1	Division Engineer US Army Engineer Division Fort Belvoir, VA 22060

DISTRIBUTION LIST

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	Director US Army Engineer Waterways Experiment Station ATTN: WESNP, Mr.L.F. Ingram P.O. Box 631 Vicksburg, MS 39180	3	Commander US Army Armament Materiel Readiness Command ATTN: Joint Army-Navy- Air Force Conventional Ammunition Prof Coord GP/E. Jordan Rock Island, IL 61299
1	Commander US Army Construction Engineering Research Lab P.O. Box 4005 Champaign, IL 61820	1	Commander US Army Rock Island Arsenal Rock Island, IL 61299
1	Commander US Army Materiel Development and Readiness Command ATTN: DRCDMD-ST 5001 Eisenhower Avenue Alexandria, VA 22333	1	Commander US Army ARRADCOM Benet Weapons Laboratory ATTN: DRDAR-LCB-TL Watervliet, NY 12189
1	Commander US Army Materiel Development and Readiness Command ATTN: DRCSF, Mr. L. Crawford 5001 Eisenhower Avenue Alexandria, VA 22333	1	Commander Pine Bluff Arsenal Pine Bluff, AR 71601
3	Commander US Army Armament Research and Development Command ATTN: DRDAR-LC DRDAR-TSS(2 cys) Dover, NJ 07801	1	Commander Cornhusker Army Ammunition Plant Grand Island, NE 68801
2	Commander US Army Armament Material Readiness Command ATTN: DRSAR-LEP-L, Tech Lib DRSAR-SA Rock Island, IL 61299	1	Commander Indiana Army Ammunition Plant Charlestown, IN 47111
		1	Commander Iowa Army Ammunition Plant Burlington, IA 52502
		1	Commander Joliet Army Ammunition Plant Joliet, IL 60436
		1	Commander Kansas Army Ammunition Plant Parsons, KS 67357

DISTRIBUTION LIST

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	Commander Lone Star Army Ammunition Plant Texarkana, TX 75502	1	Commander US Army Communications Research and Development Command DRDCO-PPA-SA Fort Monmouth, NJ 07703
1	Commander Longhorn Army Ammunition Plant Marshall, TX 75671	1	Commander US Army Electronics Research and Development Command Technical Support Activity ATTN: DELSD-L Fort Monmouth, NJ 07703
1	Commander Louisiana Army Ammunition Plant Shreveport, LA 71102	1	Commander US Army Harry Diamond Labs ATTN: DELHD-TI 2800 Powder Mill Road Adelphi, MD 20783
1	Commander Milan Army Ammunition Plant Milan, TN 38358	3	Commander US Army Missile Command ATTN: DRDMI-R DRDMI-YDL DRDMI-RSS, Mr. B. Cobb Redstone Arsenal, AL 35809
1	Commander Radford Army Ammunition Plant Radford, VA 24141	2	Commander US Army Missile Command ATTN: DRSMI-RX, Mr. W. Thomas DRSMI-RR, Mr. L. Lively Redstone Arsenal, AL 35809
1	Commander Ravenna Army Ammunition Plant Ravenna, OH 44266	1	Commander US Army Mobility Equipment Research & Development Command ATTN: DRDFB-ND, Mr. R.L. Brooke Fort Belvoir, VA 22060
1	Commander US Army Aviation Research and Development Command ATTN: DRSAB-E 12th and Spruce Streets St. Louis, MO 63166	1	Commander US Army Natick Research and Development Command ATTN: DRXRE, Dr. D. Sieling Natick, MA 01762
1	Director US Army Air Mobility Research and Development Laboratory Ames Research Center Moffett Field, CA 94035		
2	Director Léwis Directorate US Army Air Mobility Research and Development Command Lewis Research Center ATTN: Mail Stop 77-5 21000 Brookpark Road Cleveland, OH 44135		

DISTRIBUTION LIST

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
2	Commander US Army Tank Automotive Rsch and Development Command ATTN: DRDTA DRDTA-UL Warren, MI 48090	1	Commander US Army Research Office P.O. Box 12211 Research Triangle Park NC 27709
1	Commander Dugway Proving Ground ATTN: STEDP-TO-H, Mr. Miller Dugway, UT 84022	1	Commander US Army TRADOC Systems Analysis Activity ATTN: ATAA-SL (Tech Lib) White Sands Missile Range NM 88002
1	Director DARCOM Field Safety Activity ATTN: DRXOS-ES Charlestown, IN 47111	1	Commandant US Army Engineer School ATTN: ATSE-CD Fort Belvoir, VA 22060
1	Director DARCOM, ITC ATTN: Dr. Chiang Red River Depot Texarkana, TX 75501	1	Assistant Secretary of the Navy (Research & Development) Navy Department Washington, DC 20350
1	Commander US Army Foreign Science and Technology Center ATTN: Rsch & Data Branch Federal Office Building 220 - 7th Street, NE Charlottesville, VA 22901	5	Chief of Naval Operation ATTN: OP-41, C. Ferraro, Jr. OP-41B, CPT S.N. Howard OP-411, CPT F. Jonasz OP-754 OP-985FZ Department of the Navy Washington, DC 20350
1	Commander US Army Materials and Mechanics Research Center ATTN: DRXMR-ATL Watertown, MA 02172	1	Commander Bureau of Naval Weapons ATTN: Code F121 Mr. H. Roylance Department of the Navy Washington, DC 20360
1	Commander US Army TRADOC Systems Analysis Activity ATTN: ATAA-SL (Tech Lib) White Sands Missile Range NM 88002	1	Commander Naval Air Systems Command ATTN: AIR-532 Washington, DC 20361

DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Commander Naval Facilities Engineering Command ATTN: Code 045, Mr. Tyrrell 200 Stovall Street Alexandria, VA 22332	2	Commander Naval Surface Weapons Center ATTN: Code 241, Mr. Proctor R-15 Silver Spring, MD 20910
1	Commander Naval Sea Systems Command ATTN: SEA-04H, Mr. C.P. Jones Washington, DC 20362	2	Commander Naval Weapons Center ATTN: Code 0632, W.F. Finder China Lake, CA 93555
1	Commander Naval Sea Systems Command ATTN: SEA-0333 Washington, DC 20362	1	Commander Naval Weapons Support Center Crane, IN 47522
2	Commander David W. Taylor Naval Ship Research & Development Center ATTN: Mr. A. Wilner, Code 1747 Dr. W.W. Murray, Code 17 Bethesda, MD 20084	2	Commander Naval Explosive Ord Disposal Facility ATTN: Code 501, L. Wolfson Code D, Mr. E. Rice Indian Head, MD 20640
1	Commander Naval Ship Research and Development Center Facility ATTN: Mr. Lowell T. Butt Underwater Explosions Research Division Portsmouth, VA 23709	1	Commander Naval Weapons Evaluation Facility ATTN: Document Control Kirtland AFB Albuquerque, NM 87117
3	Commander Naval Surface Weapons Center ATTN: E-23, Mr. J.J. Walsh Mr. J.C. Talley Dr. W. Soper Dahlgren, VA 22448	1	Officer in Charge Civil Engineering Lab ATTN: Code L51 Naval Construction Bat Center Port Hueneme, CA 93041
3	Commander Naval Surface Weapons Center ATTN: Dr. Leon Schindel Dr. Victor Dawson Dr. P. Huang Silver Spring, MD 20910	1	Commander Naval Research Laboratory ATTN: Code 2027, Tech Lib Washington, DC 20375
		2	Superintendent Naval Postgraduate School ATTN: Tech Reports Sec. Code 57, Prof R. Ball Monterey, CA 93940

DISTRIBUTION LIST

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	HQ USAF (AFNIE-CA) Washington, DC 20330	2	HQ USAF Director of Aerospace Safety ATTN: IDG/AFISC(SEV) COL J.E. McQueen Norton AFB, CA 92409
3	HQ USAF (AFRIDQ; AFRDOSM; AFRDPM) Washington, DC 20330	1	HQ USAF (IDG/AFISC (SEW) COL T.C. Pritchett Norton AFB, CA 92409
1	AFSC (DSCPSL) Andrews AFB Washington, DC 20331	1	AFCEC (DE-LTC Walkup) Tyndall AFB, FL 32401
1	AFSC (IGFG) Andrews AFB Washington, DC 20334	1	AFFDL(FBE, Mr.R.M. Bader) Wright-Patterson AFB, OH 45433
1	AFRPL (M. Raleigh) Edwards AFB, CA 93523	2	AFLC (MMWM/CPT D. Rideout; IGYE/K. Shopker) Wright-Patterson AFB, OH 45433
1	ADTC (DLOCL, Tech Lib) Eglin AFB, FL 32542	3	AFML (LLN, Dr. T. Nicholas; MAS; MBC, Mr. D. Schmidt) Wright-Patterson AFB, OH 45433
1	ADTC (DOM/S Reither) Eglin AFB, FL 32542	1	FTD (ETD) Wright-Patterson AFB, OH 45433
2	AFATL (DLYV, P. Nash) Eglin AFB, FL 32542	1	Research Director - Pittsburgh Mining & Safety Research Cen ATTN: Mr. Richard W. Watson Bureau of Mines, Dept. of the Interior 4800 Forbes Avenue Pittsburgh, PA 15213
1	AFATL (DLYV, Mr.R.L. McGuire) Eglin AFB, FL 32542	1	Institute of Makers of Explosives ATTN: Mr. Harry Hampton Graybar Building, Rm 2449 420 Lexington Avenue New York, NY 10017
1	AFTAWC (OA) Eglin AFB, FL 32542		
1	Ogden ALC/MMWRE ATTN: (Mr. Ted E. Comins) Hill AFB, UT 84406		
5	AFWL (DEO, Mr. F.H. Peterson; SYT, MAJ W.A. Whitaker; SRR; WSUL; SR) Kirtland AFB, NM 87117		

DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Headquarters Energy Research and Development Administration Department of Military Applications Washington, DC 20545	1	Director National Aeronautics and Space Administration Marshall Space Flight Center Huntsville, AL 35812
1	Director Division of Operational Safety Department of Energy ATTN: Carlo Ferrara, Jr. Washington, DC 20545	1	Director National Aeronautics and Space Administration Scientific and Technical Information Facility P.O. Box 8757 Baltimore/Washington International Airport, MD 21240
1	Albuquerque Operations Office Energy Research and Development Administration ATTN: ODI P.O. Box 5400 Albuquerque, NM 87115	1	National Academy of Sciences ATTN: Mr. D.G. Groves 2101 Constitution Avenue, NW Washington, DC 20418
1	Director Lawrence Livermore Laboratory Technical Information Division P.O. Box 808 Livermore, CA 94550	1	Aeronautical Research Associates of Princeton, Inc. ATTN: Dr. C. Donaldson 50 Washington Road Princeton, NJ 08540
1	Director Los Alamos Scientific Lab ATTN: Dr. J. Taylor P.O.Box 1663 Los Alamos, NM 87544	1	Aerospace Corporation P.O. Box 95085 Los Angeles, CA 90045
2	National Aeronautics and Space Administration Aerospace Safety Research and Data Institute ATTN: Mr. S. Weiss Mail Stop 6-2 Mr. R. Kemp Mail Stop 6-2 Lewis Research Center Cleveland, OH 44135	1	Agbabian Associates ATTN: Dr. D.P. Reddy 250 N Nash Street El Segundo, CA 90245
		2	AVCO Corporation Structures and Mechanics Dept ATTN: Dr. William Broding Mr. J. Gilmore 201 Lowell Street Wilmington, MA 01887

DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
2	Battelle Columbus Laboratories ATTN: Dr. L.E. Hulbert Mr. J.E. Backofen, Jr. 505 King Avenue Columbus, OH 43201	3	Kaman Sciences Corporation ATTN: Dr.F.H. Shelton Dr. D. Sachs Dr. R. Keefe 1500 Garden of the Gods Road Colorado Springs, CO 80907
1	Black & Veatch Consulting Engineers ATTN: Mr. H.L. Callahan 1500 Meadow Lake Parkway Kansas City, MO 64114	1	Knolls Atomic Power Laboratory ATTN: Dr. R.A. Powell Schenectady, NY 12309
2	The Boeing Company Aerospace Group ATTN: Dr. Peter Grafton Dr. D. Strome Mail Stop 8C-68 Seattle, WA 98124	2	Martin Marietta Laboratories ATTN: Dr. P.F. Jordan Mr. R. Goldman 1450 S. Rolling Road Baltimore, MD 21227
1	General American Research Div. General American Transportation Corp. ATTN: Dr. J.C. Shang 7449 N. Natchez Avenue Niles, IL 60648	1	Mason & Hangar-Silas Mason Co., Incorporated Pantex Plant ATTN: Director of Development P.O. Box 647 Amarillo, TX 79177
1	Hercules, Inc. ATTN: Billings Brown Box 93 Magna, UT 84044	1	McDonnell Douglas Astronautics Western Division ATTN: Dr. Lea Cohen 5301 Bosla Avenue Huntington Beach, CA 92647
1	J.G. Engineering Research Associates 3831 Menlo Drive Baltimore, MD 21215	1	Monsanto Research Corporation Mound Laboratory ATTN: Frank Neff Miamisburg, OH 45342
2	Kaman-AviDyne ATTN: Dr. N.P. Hobbs Mr. S. Criscione Northwest Industrial Park 83 Second Avenue Burlington, MA 01803	1	Physics International 2700 Merced Street San Leandro, CA 94577
		1	R&D Associates ATTN: Mr. John Lewis P.O. Box 9695 Marina del Rey, CA 90291

DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
2	Sandia Laboratories ATTN: Infor Distr Division Dr. W.A. vonRieseemann Albuquerque, NM 87115	3	Southwest Research Institute ATTN: Dr. H.N. Abramson Dr. W.E. Baker Dr. U.S. Lindholm 8500 Culebra Road San Antonio, TX 78228
1	Science Applications, Inc. 8th Floor 2361 Jefferson Davis Highway Arlington, VA 22202	1	Texas A&M University Department of Aerospace Engineering ATTN: Dr. James A Stricklin College Station, TX 77843
1	Brown University Division of Engineering ATTN: Prof R. Clifton Providence, RI 02912	1	University of Alabama ATTN: Dr. T.L. Cost P.O. Box 2908 University, AL 35486
1	Florida Atlantic University Dept of Ocean Engineering ATTN: Prof K.K. Stevens Boca Raton, FL 33432	1	University of Delaware Department of Mechanical and Aerospace Engineering ATTN: Prof J.R. Vinson Newark, DE 19711
1	Georgia Institute of Technology ATTN: Dr. S. Atluri 225 North Avenue, NW Atlanta, GA 30332		<u>Aberdeen Proving Ground</u>
1	IIT Research Institute ATTN: Mrs. H. Napadensky 10 West 35 Street Chicago, IL 60616		Dir, USAMSAA ATTN: DRXSY-D Mr. R. Norman, GWD DRXSY-MP, H. Cohen
1	Lovelace Research Institute ATTN: Dr. E.R. Fletcher P.O. Box 5890 Albuquerque, NM 87115		Cdr/Dir, CSL, EA ATTN: DRDAR-CLJ-L Cdr, USATECOM ATTN: DRSTE-TO-F Cdr, US Army Toxic and Hazardous Materials Agcy, Bldg E4585 ATTN: DRXTA-TE
1	Massachusetts Institute of Technology Aeroelastic and Structures Research Laboratory ATTN: Dr. E.A. Witmer Cambridge, MA 02139		Dir, Wpns Sys Concepts Team Bldg E3516, EA ATTN: DRDAR-ACW

USER EVALUATION OF REPORT

Please take a few minutes to answer the questions below; tear out this sheet and return it to Director, US Army Ballistic Research Laboratory, ARRADCOM, ATTN: DRDAR-TSB, Aberdeen Proving Ground, Maryland 21005. Your comments will provide us with information for improving future reports.

1. BRL Report Number _____

2. Does this report satisfy a need? (Comment on purpose, related project, or other area of interest for which report will be used.)

3. How, specifically, is the report being used? (Information source, design data or procedure, management procedure, source of ideas, etc.) _____

4. Has the information in this report led to any quantitative savings as far as man-hours/contract dollars saved, operating costs avoided, efficiencies achieved, etc.? If so, please elaborate.

5. General Comments (Indicate what you think should be changed to make this report and future reports of this type more responsive to your needs, more usable, improve readability, etc.) _____

6. If you would like to be contacted by the personnel who prepared this report to raise specific questions or discuss the topic, please fill in the following information.

Name: _____

Telephone Number: _____

Organization Address: _____

